

QUOTATION OF WORK

Name of Work: Repair and Maintenance of Ground Floor Room of the Waqf Board Building at Broadway Ernakulam.

Sl. No.	Description	Qty	Unit	Rate (₹)	Amount (₹)
1	M/L for Plain Cement Concrete mix (1:3:6) 150mm thick in flooring	0.70	m ³		
2	M/L for 150mm thick Solid block masonry in CM 1:6	0.80	m ³		
3	M/L for rendering 12mm thick Cement plaster on fair face & brick work in CM 1:4 in internal wall surface	52.00	m ²		
4	M/L for laying Vetrified tiles in floors and laid with 12mm thick Cement screed including grouting of joints	4.80	m ²		
5	M/L for preparation of wall surface and applying two coats Oil Bound Distemper	160.00	m ²		
6	M/L for preparation of wooden ceiling surface and applying One coat Enamel paint	90.00	m ²		
7	M/L for preparation of steel surface and applying One coat Enamel paint	48.00	m ²		
8	M/L for Concrete covering of Rolling Shutter	3.00	Nos		
Grand Total					

